

Braintree Local Plan

Preferred Option Assessment

Highways/Transport Planning

March 2017



Appendix G: Junction Modelling Results

The following tables outline the results from the junction models run using both Junctions 9 and LinSig. There are one or more results tables for each junction. The first table for each junction is a do nothing scenario for the junction i.e. the existing layout with the forecast traffic growth for 2033. Some junctions have been modelled with the all movements junction on the A12 at junction 24 and therefore a table depicting the result of that model run is included. Some junctions have been modelled with mitigation applied to them and the model results of these are also included. Where mitigation has been applied a sentence describing this has been included.

A131 – London Road, Great Notley

Junction arms:

A – A131 Great Notley Bypass

B – London Road north-east

C – London Road south-east

D – A131 Great Leighs Bypass

Existing Layout

		A	B	C	D
AM					
Base Year	RFC	0.36	0.57	0.16	0.29
	Delay(s)	2.34	5.79	4.59	2.01
Scenario 1	RFC	0.68	0.91	0.24	0.69
	Delay(s)	5.09	27.94	7.81	4.58
Scenario 2	RFC	0.70	0.92	0.25	0.70
	Delay(s)	5.43	31.65	8.06	4.75
Scenario 3	RFC	0.72	0.93	0.25	0.71
	Delay(s)	5.81	36.32	8.32	4.95
PM					
Base Year	RFC	0.39	0.31	0.22	0.50
	Delay(s)	2.97	3.29	3.51	2.6
Scenario 1	RFC	1.02	0.52	0.35	0.81
	Delay(s)	60.21	6.23	6.29	7.11
Scenario 2	RFC	1.06	0.52	0.36	0.82
	Delay(s)	127.25	6.26	6.30	7.59
Scenario 3	RFC	1.10	0.52	0.36	0.84
	Delay(s)	229.08	6.20	6.28	8.14

Background growth only

		A	B	C	D
AM					
Base Year	RFC	0.36	0.57	0.16	0.29
	Delay(s)	2.34	5.79	4.59	2.01
Background Growth	RFC	0.44	0.55	0.16	0.33
	Delay(s)	2.77	5.65	4.78	2.1
PM					
Base Year	RFC	0.39	0.31	0.22	0.50
	Delay(s)	2.97	3.29	3.51	2.6
Background Growth	RFC	0.47	0.28	0.24	0.62
	Delay(s)	3.66	3.31	3.8	3.5

Mitigation Layout – Widening of A131N and London Road NE approaches

		A	B	C	D
AM					
Base Year	RFC	0.36	0.57	0.16	0.29
	Delay(s)	2.34	5.79	4.59	2.01
Scenario 1	RFC	0.54	0.81	0.24	0.69
	Delay(s)	2.80	13.08	7.92	4.59
Scenario 2	RFC	0.56	0.82	0.25	0.70
	Delay(s)	2.90	13.98	8.19	4.76
Scenario 3	RFC	0.57	0.83	0.25	0.71
	Delay(s)	3.00	15.03	8.48	4.96
PM					
Base Year	RFC	0.39	0.31	0.22	0.50
	Delay(s)	2.97	3.29	3.51	2.6
Scenario 1	RFC	0.78	0.47	0.36	0.81
	Delay(s)	7.12	4.98	6.62	7.11
Scenario 2	RFC	0.81	0.48	0.37	0.82
	Delay(s)	8.10	5.08	6.80	7.59
Scenario 3	RFC	0.84	0.48	0.37	0.84
	Delay(s)	9.41	5.20	6.99	8.14

Aetheric Road – Pierrefitte Way, Braintree

Junction arms:

- A – Aetheric Road
- B – Rayne Road east
- C – Pierrefitte Way
- D – London Road

Existing Layout

		A – BCD	B – ACD	C - AD	C – B	D -ABC
AM						
Base Year	Deg. Of Sat	104.2%	8.6%	99.6%	74%	104%
	Delay / PCU	173.2	42	133.8	75.3	173.2
Scenario 1	Deg. Of Sat	91.4%	8.4%	87.1%	75%	92.1%
	Delay / PCU	44.7	41.4	85.3	81	75.3
Scenario 2	Deg. Of Sat	93.3%	8.4%	88.1%	75%	93.3%
	Delay / PCU	48.1	41.4	87.3	81	79.7
Scenario 3	Deg. Of Sat	98.4%	8.6%	95.9%	80.4%	97.8%
	Delay / PCU	68.8	40.2	120.8	91.4	104.6
PM						
Base Year	Deg. Of Sat	95.3%	48.9%	94.2%	46.6%	94%
	Delay / PCU	94.1	53.5	89.1	51.6	62
Scenario 1	Deg. Of Sat	104.6%	53.8%	103.3%	48.4%	99.7%
	Delay / PCU	144.1	71.2	162.7	50	145.7
Scenario 2	Deg. Of Sat	105.7%	53.4%	105%	49.1%	106.2%
	Delay / PCU	159.4	71.4	186.3	50.2	226.7
Scenario 3	Deg. Of Sat	108.2%	53.3%	106.2%	49.9%	108.1%
	Delay / PCU	197.6	71.3	204	50.4	252.3

Background growth only

		A – BCD	B – ACD	C – AD	C – B	D – ABC
AM						
Base Year	Deg. Of Sat	104.2%	8.6%	99.6%	74%	104%
	Delay / PCU	173.2	42	133.8	75.3	173.2
Background Growth	Deg. Of Sat	76.2%	7.5%	74.2%	67.4%	75.2%
	Delay / PCU	37.1	35.8	68.4	71.8	48.1
PM						
Base Year	Deg. Of Sat	95.3%	48.9%	94.2%	46.6%	94%
	Delay / PCU	94.1	53.5	89.1	51.6	62
Background Growth	Deg. Of Sat	70.2%	49.7%	70.9%	43.3%	70.6%
	Delay / PCU	34.5	62.5	50.9	46.7	57.0

Broad Road, Braintree

Junction arms:
A – A131 north
B – A131 south
C – Broad Road

Existing Layout

		A	B	C
AM				
Base Year	RFC	0.74	0.51	0.38
	Delay(s)	8.58	4.85	5.61
Scenario 1	RFC	0.63	1.33	0.35
	Delay(s)	6.54	952.23	6.40
Scenario 2	RFC	0.66	OC	0.35
	Delay(s)	6.98	OC	6.33
Scenario 3	RFC	0.69	OC	0.35
	Delay(s)	7.75	OC	6.22
PM				
Base Year	RFC	0.54	0.51	0.61
	Delay(s)	5.22	4.15	9.85
Scenario 1	RFC	1.20	0.84	1.08
	Delay(s)	327.35	12.46	145.96
Scenario 2	RFC	1.26	0.85	1.11
	Delay(s)	483.38	13.37	180.63
Scenario 3	RFC	1.32	0.87	1.13
	Delay(s)	643.91	14.33	230.93

Background growth only

		A	B	C
AM				
Base Year	RFC	0.74	0.51	0.38
	Delay(s)	8.58	4.85	5.61
Background Growth	RFC	0.42	0.49	0.25
	Delay(s)	4.08	4.83	4.69
PM				
Base Year	RFC	0.54	0.51	0.61
	Delay(s)	5.22	4.15	9.85
Background Growth	RFC	0.57	0.50	0.58
	Delay(s)	5.47	4.07	9.05

Mitigation Layout – Left turn slips on all arms

		A	B	C
AM				
Base Year	RFC	0.74	0.51	0.38
	Delay(s)	8.58	4.85	5.61
Scenario 1	RFC	0.44	0.66	0.36
	Delay(s)	4.03	6.21	6.67
Scenario 2	RFC	0.46	0.71	0.39
	Delay(s)	4.20	7.34	7.33
Scenario 3	RFC	0.49	0.77	0.41
	Delay(s)	4.48	9.28	8.12
PM				
Base Year	RFC	0.54	0.51	0.61
	Delay(s)	5.22	4.15	9.85
Scenario 1	RFC	0.28	0.50	0.92
	Delay(s)	3.54	3.41	38.25
Scenario 2	RFC	0.28	0.51	0.95
	Delay(s)	3.57	3.46	47.17
Scenario 3	RFC	0.28	0.52	0.97
	Delay(s)	3.6	3.51	56.95

Church Lane – Bradford Street, Braintree

Junction arms:

A – B1053 Church Lane

B – Convent Hill

C – Bradford Street

Existing Layout

		A	B	C
AM				
Base Year	RFC	0.80	1.00	0.62
	Delay(s)	23.90	69.86	8.72
Scenario 1	RFC	0.67	OC	0.55
	Delay(s)	15.04	OC	8.91
Scenario 2	RFC	0.69	OC	0.56
	Delay(s)	15.85	OC	9.12
Scenario 3	RFC	0.71	OC	0.57
	Delay(s)	16.79	OC	9.37
PM				
Base Year	RFC	0.99	0.56	0.93
	Delay(s)	78.21	8.82	32.58
Scenario 1	RFC	OC	0.89	1.31
	Delay(s)	OC	35.87	823.98
Scenario 2	RFC	OC	0.91	1.33
	Delay(s)	OC	40.84	875.61
Scenario 3	RFC	OC	0.92	1.34
	Delay(s)	OC	46.28	921.48

Background growth only

		A	B	C
AM				
Base Year	RFC	0.80	1.00	0.62
	Delay(s)	23.90	69.86	8.72
Background Growth	RFC	0.54	1.32	0.43
	Delay(s)	10.91	979.09	6.30
PM				
Base Year	RFC	0.99	0.56	0.93
	Delay(s)	78.21	8.82	32.58
Background Growth	RFC	OC	0.53	1.04
	Delay(s)	OC	9.06	122.21

Courtauld Road – Coggeshall Road, Braintree

Junction arms:

- 1A – Courtauld Road north
- 1B – Link road north
- 1C – Coggeshall Road west
- 2A – Link road south
- 2B – Coggeshall Road east
- 2C – Courtauld Road south

Existing Layout

		1A	1B	1C	2A	2B	2C
AM							
Base Year	RFC	0.72	0.62	0.78	0.93	0.82	0.41
	Delay(s)	10.59	7.44	25.11	29.66	18.60	8.07
Scenario 1	RFC	0.64	0.71	0.62	0.86	0.83	0.59
	Delay(s)	8.10	9.83	17.07	20.25	21.29	11.35
Scenario 2	RFC	0.64	0.72	0.63	0.86	0.84	0.61
	Delay(s)	8.10	9.99	17.25	20.92	22.22	11.88
Scenario 3	RFC	0.64	0.72	0.63	0.87	0.85	0.63
	Delay(s)	8.10	10.20	17.51	21.64	23.55	12.52
PM							
Base Year	RFC	0.53	0.61	0.96	0.90	0.65	0.67
	Delay(s)	6.56	6.97	64.93	22.55	9.83	12.98
Scenario 1	RFC	0.51	0.87	OC	0.79	0.84	0.89
	Delay(s)	6.11	20.00	OC	13.89	20.84	41.90
Scenario 2	RFC	0.51	0.88	OC	0.79	0.84	0.92
	Delay(s)	6.09	20.84	OC	14.17	21.23	51.14
Scenario 3	RFC	0.51	0.88	OC	0.79	0.84	0.94
	Delay(s)	6.07	21.35	OC	14.55	21.46	62.61

Background growth only

		1A	1B	1C	2A	2B	2C
AM							
Base Year	RFC	0.72	0.62	0.78	0.93	0.82	0.41
	Delay(s)	10.59	7.44	25.11	29.66	18.60	8.07
Background Growth	RFC	0.99	0.66	0.68	1.18	0.86	0.46
	Delay(s)	84.36	8.31	19.47	514.62	26.18	8.60
PM							
Base Year	RFC	0.53	0.61	0.96	0.90	0.65	0.67
	Delay(s)	6.56	6.97	64.93	22.55	9.83	12.98
Background Growth	RFC	0.50	0.83	OC	0.75	0.81	0.75
	Delay(s)	5.90	15.00	OC	11.52	17.70	19.88

Cressing Road – Coggeshall Road, Braintree

Existing Layout

Junction arms:

A – Coggeshall Road W

B – Coggeshall Road E

C – Cressing Road

D – Marlborough Road

EB Link – Eastbound Coggeshall Road Link

WB Link – Westbound Coggeshall Road Link

		A - BCD	WB Link	EB Link	D - ABC	B - ACD	C - ABD
AM							
Base Year 2015	Deg. Of Sat	36.5%	80.5%	40.6%	97.5%	100.2%	100.2%
	Delay / PCU	9.4	30.5	6.6	135	87.9	149.5
Scenario 1 2033	Deg. Of Sat	57.2	81.2	49.4	OC	OC	53.9
	Delay / PCU	11.2	38.7	10.3	OC	OC	44.9
Scenario 2 2033	Deg. Of Sat	60	78.4	52	OC	OC	54.1
	Delay / PCU	11.4	37.9	11.1	OC	OC	45
Scenario 3 2033	Deg. Of Sat	56	72.8	50.2	138.2	139.9	72.1
	Delay / PCU	9.5	24.8	10.6	636.4	601.7	73.2
PM							
Base Year 2015	Deg. Of Sat	73	49.8	70.2	49.5	117	117.6
	Delay / PCU	16.6	26.5	11.2	60.9	325.8	351.5
Scenario 1 2033	Deg. Of Sat	79.9	37.4	77.5	71.1	OC	OC
	Delay / PCU	13.5	11.3	12.5	76.6	OC	OC
Scenario 2 2033	Deg. Of Sat	81.9	36.4	79.3	73	OC	OC
	Delay / PCU	14.3	9.7	13	78.9	OC	OC
Scenario 3 2033	Deg. Of Sat	80.3	45.1	73.3	99	OC	OC
	Delay / PCU	17.5	31.6	10.9	211.1	OC	OC

Background growth only

		A - BCD	WB Link	EB Link	D - ABC	B - ACD	C - ABD
AM							
Base Year 2015	Deg. Of Sat	36.5%	80.5%	40.6%	97.5%	100.2%	100.2%
	Delay / PCU	9.4	30.5	6.6	135	87.9	149.5
Background Growth	Deg. Of Sat	47.9	95.5	39.9	116	122.9	45.9
	Delay / PCU	11.8	63	9.1	352.7	392.3	39.3
PM							
Base Year 2015	Deg. Of Sat	73	49.8	70.2	49.5	117	117.6
	Delay / PCU	16.6	26.5	11.2	60.9	325.8	351.5
Background Growth	Deg. Of Sat	70.6	49.1	69.7	55.7	198	195.4
	Delay / PCU	11.5	25.3	10.6	64	1004.5	995.4

Mitigation Layout – Double mini-roundabout

Junction arms:

1A – Coggeshall Road W

1B – Link road

1C – Cressing Road

2A – Coggeshall Road E

2B – Link road

2C – Marlborough Road

		1A	1B	1C	2A	2B	2C
AM							
Scenario 1	RFC	0.59	1.08	0.05	1.19	0.59	0.52
	Delay(s)	6.96	179.05	4.94	371.92	8.63	11.73
Scenario 2	RFC	0.62	1.08	0.05	1.19	0.62	0.53
	Delay(s)	7.47	183.36	4.91	371.87	9.33	12.39
Scenario 3	RFC	0.64	1.08	0.05	1.19	0.65	0.54
	Delay(s)	7.98	187.71	4.88	371.82	10.02	12.99
PM							
Scenario 1	RFC	0.94	0.98	0.45	0.98	1.13	0.33
	Delay(s)	41.93	63.66	9.44	63.91	259.03	15.01
Scenario 2	RFC	0.97	0.98	0.45	0.98	1.15	0.33
	Delay(s)	54.35	64.23	9.42	63.91	291.76	15.04
Scenario 3	RFC	0.99	0.98	0.45	0.98	1.17	0.33
	Delay(s)	72.96	64.07	9.42	63.91	322.16	15.07

Cuckoo Way, Great Notley

Junction arms:

A – A131 north

B – Cuckoo Way

C – A131 south

D – New arm for development

Existing Layout

		A	B	C	D
AM					
Base Year	RFC	0.31	0.31	0.53	N/A
	Delay(s)	2.08	3.07	4.76	N/A
Scenario 1	RFC	0.79	0.58	OC	0.32
	Delay(s)	7.07	7.72	OC	20.00
Scenario 2	RFC	0.81	0.60	OC	0.34
	Delay(s)	7.56	8.07	OC	21.50
Scenario 3	RFC	0.81	0.60	OC	0.35
	Delay(s)	7.67	8.36	OC	21.96
PM					
Base Year	RFC	0.37	0.31	0.51	N/A
	Delay(s)	2.22	2.92	4.25	N/A
Scenario 1	RFC	0.86	0.54	1.03	0.78
	Delay(s)	10.82	7.67	94.78	39.88
Scenario 2	RFC	0.90	0.57	1.09	0.80
	Delay(s)	15.10	8.58	150.46	44.78
Scenario 3	RFC	0.94	0.60	1.14	0.82
	Delay(s)	22.98	9.66	214.39	48.83

Background growth only

		A	B	C	D
AM					
Base Year	RFC	0.31	0.31	0.53	N/A
	Delay(s)	2.08	3.07	4.76	N/A
Background Growth	RFC	0.41	0.36	0.62	N/A
	Delay(s)	2.52	3.64	6.09	N/A
PM					
Base Year	RFC	0.37	0.31	0.51	N/A
	Delay(s)	2.22	2.92	4.25	N/A
Background Growth	RFC	0.40	0.29	0.55	N/A
	Delay(s)	2.32	2.98	4.79	N/A

Mitigation Layout – Widening of A131 approaches

		A	B	C	D
AM					
Base Year	RFC	0.31	0.31	0.53	N/A
	Delay(s)	2.08	3.07	4.76	N/A
Scenario 1	RFC	0.75	0.65	0.92	0.18
	Delay(s)	5.62	10.25	19.74	9.55
Scenario 2	RFC	0.78	0.68	0.95	0.20
	Delay(s)	6.41	11.69	28.17	10.26
Scenario 3	RFC	0.80	0.71	0.98	0.21
	Delay(s)	7.38	13.38	42.18	10.93
PM					
Base Year	RFC	0.37	0.31	0.51	N/A
	Delay(s)	2.22	2.92	4.25	N/A
Scenario 1	RFC	0.73	0.54	0.60	0.40
	Delay(s)	4.89	7.83	4.22	7.86
Scenario 2	RFC	0.77	0.58	0.64	0.42
	Delay(s)	5.86	8.99	4.67	8.51
Scenario 3	RFC	0.81	0.62	0.67	0.44
	Delay(s)	7.22	10.50	5.21	9.24

Deanery Hill, Braintree

Junction arms:

A – Deanery Hill west

B – Deanery Hill east

C – Panfield Lane

Existing Layout

		B-C	B-A	C-AB
AM				
Base Year	RFC	0.16	0.16	0.30
	Delay(s)	6.89	10.99	8.19
Scenario 1	RFC	OC	OC	OC
	Delay(s)	OC	OC	OC
Scenario 2	RFC	OC	OC	OC
	Delay(s)	OC	OC	OC
Scenario 3	RFC	OC	OC	OC
	Delay(s)	OC	OC	OC
PM				
Base Year	RFC	0.16	0.21	0.21
	Delay(s)	7.03	9.78	7.04
Scenario 1	RFC	OC	OC	OC
	Delay(s)	OC	OC	OC
Scenario 2	RFC	OC	OC	OC
	Delay(s)	OC	OC	OC
Scenario 3	RFC	OC	OC	OC
	Delay(s)	OC	OC	OC

Background growth only

		B-C	B-A	C-AB
AM				
Base Year	RFC	0.16	0.16	0.30
	Delay(s)	6.89	10.99	8.19
Background Growth	RFC	0.08	0.13	0.34
	Delay(s)	8.78	15.5	11.6
PM				
Base Year	RFC	0.16	0.21	0.21
	Delay(s)	7.03	9.78	7.04
Background Growth	RFC	0.13	0.21	0.18
	Delay(s)	7.09	9.89	6.64

Mitigation Layout - Signalised

		A - BC	B - AC	C - AB
AM				
Scenario 1	Deg. Of Sat	63.8%	83%	83.7%
	Delay / PCU	35.5	21	19.5
Scenario 2	Deg. Of Sat	63.6%	85.9%	85.8%
	Delay / PCU	34.5	23.6	21.8
Scenario 3	Deg. Of Sat	63.6%	87.7%	88%
	Delay / PCU	33.6	26.1	24.5
PM				
Scenario 1	Deg. Of Sat	61.5%	59.3%	61.9%
	Delay / PCU	25.1	20.4	17.5
Scenario 2	Deg. Of Sat	64.3%	59.8%	64.9%
	Delay / PCU	25.8	20.7	18.3
Scenario 3	Deg. Of Sat	67.3%	60.2%	67.2%
	Delay / PCU	26.6	20.9	18.9

Mitigation Layout – Mini Roundabout

		A	B	C
AM				
Scenario 1	RFC	0.77	1.04	OC
	Delay(s)	28.4	88.2	OC
Scenario 2	RFC	0.79	1.08	OC
	Delay(s)	29.9	114.8	OC
Scenario 3	RFC	0.80	1.08	OC
	Delay(s)	31.3	130.7	OC
PM				
Scenario 1	RFC	0.94	0.78	0.86
	Delay(s)	63.5	27.4	37.8
Scenario 2	RFC	0.99	0.80	0.91
	Delay(s)	96.1	30.2	51.7
Scenario 3	RFC	1.04	0.82	0.95
	Delay(s)	143.5	32.4	67.9

Marks Farms, Braintree

Junction arms:

A – A131

B – A120 east

C – A120 south

D – Coggeshall Road

Existing Layout

		A	B	C	D
AM					
Base Year	RFC	0.76	0.61	0.50	0.73
	Delay(s)	17.44	14.86	2.89	10.29
Scenario 1	RFC	0.91	1.15	1.22	OC
	Delay(s)	38.85	330.60	659.14	OC
Scenario 2	RFC	1.27	OC	1.36	OC
	Delay(s)	477.81	OC	1059.37	OC
Scenario 3	RFC	1.31	OC	OC	OC
	Delay(s)	598.37	OC	OC	OC
PM					
Base Year	RFC	0.73	0.54	0.73	0.97
	Delay(s)	16.53	9.42	5.36	44.27
Scenario 1	RFC	0.90	1.15	1.22	OC
	Delay(s)	38.86	330.15	659.19	OC
Scenario 2	RFC	OC	0.92	1.21	OC
	Delay(s)	OC	42.23	616.91	OC
Scenario 3	RFC	OC	0.94	1.30	OC
	Delay(s)	OC	49.87	917.99	OC

Background growth only

		A	B	C	D
AM					
Base Year	RFC	0.76	0.61	0.50	0.73
	Delay(s)	17.44	14.86	2.89	10.29
Background Growth	RFC	0.62	0.56	0.56	0.81
	Delay(s)	12.19	9.55	3.37	14.38
PM					
Base Year	RFC	0.73	0.54	0.73	0.97
	Delay(s)	16.53	9.42	5.36	44.27
Background Growth	RFC	0.84	0.60	0.67	0.78
	Delay(s)	24.98	11.52	4.55	11.67

Effect of A12 J24 All Moves Junction

		A	B	C	D
AM					
Base Year	RFC	0.76	0.61	0.50	0.73
	Delay(s)	17.44	14.86	2.89	10.29
Scenario 1	RFC	0.83	1.14	0.99	OC
	Delay(s)	24.19	317.85	50.36	OC
Scenario 2	RFC	0.87	1.26	1.10	OC
	Delay(s)	29.90	638.30	301.73	OC
Scenario 3	RFC	0.90	1.39	1.22	OC
	Delay(s)	37.05	978.48	644.92	OC
PM					
Base Year	RFC	0.73	0.54	0.73	0.97
	Delay(s)	16.53	9.42	5.36	44.27
Scenario 1	RFC	OC	0.93	0.95	OC
	Delay(s)	OC	46.75	27.33	OC
Scenario 2	RFC	OC	0.93	1.13	OC
	Delay(s)	OC	47.04	128.40	OC
Scenario 3	RFC	OC	0.95	1.13	OC
	Delay(s)	OC	55.52	376.30	OC

Panners Interchange, Braintree/Great Notley

Junction arms:

1A – Pods Brook

1B – A131 (link)

1C – A120 west

2A – A131 (link)

2B – A120 east

2C – B1256

2D – A131 south

Existing Layout

		1A	1B	1C	2A	2B	2C	2D
AM								
Base Year	RFC	0.99	0.39	0.75	0.86	1.01	1.00	0.33
	Delay(s)	74.17	2.66	13.18	11	64.44	64.03	3.4
Scenario 1	RFC	OC	0.68	1.08	0.61	1.03	OC	0.76
	Delay(s)	OC	5.02	163.98	4.93	134.29	OC	7.58
Scenario 2	RFC	OC	0.67	1.07	0.61	1.04	OC	0.76
	Delay(s)	OC	4.99	158.11	4.97	164.22	OC	7.61
Scenario 3	RFC	OC	0.67	1.07	0.61	1.05	OC	0.77
	Delay(s)	OC	4.98	156.55	5.02	189.15	OC	7.62
PM								
Base Year	RFC	0.56	0.26	0.97	0.87	0.28	0.16	0.24
	Delay(s)	5.19	2.08	36.89	10.40	5.86	3.35	1.70
Scenario 1	RFC	1.10	0.54	OC	0.73	0.84	0.44	0.46
	Delay(s)	248.30	3.36	OC	6.07	26.15	8.78	2.54
Scenario 2	RFC	1.10	0.54	OC	0.73	0.86	0.44	0.47
	Delay(s)	251.69	3.35	OC	6.16	28.12	9.05	2.56
Scenario 3	RFC	1.10	0.54	OC	0.74	0.87	0.45	0.47
	Delay(s)	252.87	3.35	OC	6.24	30.46	9.41	2.58

Background growth only

		1A	1B	1C	2A	2B	2C	2D
AM								
Base Year	RFC	0.99	0.39	0.75	0.86	1.01	1.00	0.33
	Delay(s)	74.17	2.66	13.18	11	64.44	64.03	3.4
Background Growth	RFC	1.96	0.40	0.70	0.59	0.76	1.15	0.32
	Delay(s)	2766.97	2.74	10.91	3.56	12.55	225.08	2.69
PM								
Base Year	RFC	0.56	0.26	0.97	0.87	0.28	0.16	0.24
	Delay(s)	5.19	2.08	36.89	10.40	5.86	3.35	1.70
Background Growth	RFC	1.19	0.36	1.12	0.78	0.30	0.21	0.33
	Delay(s)	518.41	2.46	389.37	6.86	6.54	4.24	1.79

Mitigation – Widening of Pods Brook & A120 West Approaches

		1A	1B	1C	2A	2B	2C	2D
AM								
Base Year	RFC	0.99	0.39	0.75	0.86	1.01	1.00	0.33
	Delay(s)	74.2	2.7	13.2	11	64.4	64.	3.4
Scenario 1	RFC	1.25	0.62	0.88	0.88	OC	OC	0.74
	Delay(s)	693.1	4.3	30.1	15.5	OC	OC	6.9
Scenario 2	RFC	1.25	0.62	0.88	0.89	OC	OC	0.75
	Delay(s)	691.9	4.3	30.1	16	OC	OC	7
Scenario 3	RFC	1.25	0.62	0.88	0.89	OC	OC	0.75
	Delay(s)	693.4	4.3	30.1	16.5	OC	OC	7
PM								
Base Year	RFC	0.56	0.26	0.97	0.87	0.28	0.16	0.24
	Delay(s)	5.2	2.1	36.9	10.4	5.9	3.4	1.7
Scenario 1	RFC	0.62	0.54	1.31	0.80	0.97	0.47	0.46
	Delay(s)	6.7	3.3	931.5	8	70.2	9	2.6
Scenario 2	RFC	0.62	0.54	1.31	0.80	0.99	0.48	0.47
	Delay(s)	6.7	3.3	913.6	8.2	81	10.3	2.6
Scenario 3	RFC	0.62	0.54	1.31	0.80	1.01	0.48	0.47
	Delay(s)	6.7	3.3	906.3	8.3	96.4	10.8	2.6

Mitigation – Part Signalisation

N.B. Due to the number of links, only the results for the roundabout approaches have been shown.

		1A	1B	1C	2A	2B	2C	2D
AM								
Scenario 1	Degree of Saturation	OC	85.2%	52.7%	56.6%	89.5%	41.3%	OC
	Delay / PCU (s)	OC	36.1	17.1	7.4	34.8	4.7	OC
Scenario 2	Degree of Saturation	OC	91.1	63.9	65.6	94.5	42.2	OC
	Delay / PCU (s)	OC	40	17.6	9.9	47.7	5.1	OC
Scenario 3	Degree of Saturation	OC	87.9	85.2	66.1	107.3	62	OC
	Delay / PCU (s)	OC	35.7	30.9	5.3	172.7	11.7	OC
PM								
Scenario 1	Degree of Saturation	118.9	83.3	81.6	92.6	111.3	45.8	55.3
	Delay / PCU (s)	190.9	32.3	22.2	22.9	225.1	6	7.9
Scenario 2	Degree of Saturation	OC	88	89.4	95.8	109.3	39.9	59.9
	Delay / PCU (s)	OC	36	28.4	31.9	193.9	5.1	9
Scenario 3	Degree of Saturation	OC	88.2	92.6	100.2	133.2	41.8	54.7
	Delay / PCU (s)	OC	34.2	31.9	59.9	496	5.7	6.9

Springwood Drive, Braintree

Junction arms:

A – Springwood Drive north

B – Rayne Road east

C – Pods Brook Road south

D – Rayne Road west

Existing Layout

		A	B	C	D
AM					
Base Year	RFC	0.34	0.69	0.68	0.46
	Delay(s)	6.73	7.88	8.39	7.31
Scenario 1	RFC	0.89	1.01	0.94	0.65
	Delay(s)	35.82	80.06	36.61	15.97
Scenario 2	RFC	0.93	1.03	0.96	0.67
	Delay(s)	49.64	107.43	48.69	17.51
Scenario 3	RFC	0.95	1.04	0.99	0.69
	Delay(s)	60.77	130.29	66.29	19.18
PM					
Base Year	RFC	0.70	0.42	0.52	0.26
	Delay(s)	11.45	4.89	5.00	4.52
Scenario 1	RFC	0.97	0.63	0.89	0.37
	Delay(s)	56.65	8.80	22.89	7.99
Scenario 2	RFC	1.00	0.63	0.93	0.39
	Delay(s)	69.58	8.90	34.75	8.60
Scenario 3	RFC	1.02	0.64	0.98	0.41
	Delay(s)	83.21	9.08	60.04	9.13

Background growth only

		A	B	C	D
AM					
Base Year	RFC	0.34	0.69	0.68	0.46
	Delay(s)	6.73	7.88	8.39	7.31
Background Growth	RFC	0.23	0.62	0.55	0.38
	Delay(s)	5.59	6.75	6.60	6.31
PM					
Base Year	RFC	0.70	0.42	0.52	0.26
	Delay(s)	11.45	4.89	5.00	4.52
Background Growth	RFC	0.81	0.47	0.44	0.20
	Delay(s)	18.54	5.78	4.71	4.21

Mitigation Layout – Enlarged Roundabout

		A	B	C	D
AM					
Base Year	RFC	0.20	0.51	0.49	0.36
	Delay(s)	3.9	4.3	3.8	4.8
Scenario 1	RFC	0.72	0.80	0.75	0.55
	Delay(s)	12	14.3	7.7	9
Scenario 2	RFC	0.75	0.82	0.77	0.56
	Delay(s)	13.4	16	8.4	9.5
Scenario 3	RFC	0.77	0.83	0.79	0.58
	Delay(s)	14.4	16.9	9.1	10.3
PM					
Base Year	RFC	0.50	0.34	0.31	0.20
	Delay(s)	5	3.6	2.7	3.2
Scenario 1	RFC	0.63	0.49	0.64	0.32
	Delay(s)	7.1	4.9	5.6	5.3
Scenario 2	RFC	0.65	0.49	0.66	0.33
	Delay(s)	7.3	5	6.1	5.6
Scenario 3	RFC	0.66	0.50	0.70	0.34
	Delay(s)	7.6	5	6.7	5.9

A120 – Colne Road, Coggeshall

Junction arms:

A – A120 east

B – Colne Road south

C – A120 west

D – Colne Road north

Existing Layout

		B-C	B-AD	A-D	D-A	D-BC	C-B
AM							
Base Year	RFC	0.23	0.51	0.33	0.30	0.79	0.24
	Delay(s)	13.23	23.20	11.02	22.81	38.67	13.34
Scenario 1	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 2	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 3	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
PM							
Base Year	RFC	0.20	0.50	0.20	0.30	0.63	0.09
	Delay(s)	11.44	19.81	11.72	14.40	24.88	8.90
Scenario 1	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 2	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 3	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC

Background growth only

		B-C	B-AD	A-D	D-A	D-BC	C-B
AM							
Base Year	RFC	0.23	0.51	0.33	0.30	0.79	0.24
	Delay(s)	13.23	23.20	11.02	22.81	38.67	13.34
Background Growth	RFC	0.20	0.81	0.70	1.00	1.01	0.37
	Delay(s)	21.37	59.65	26.32	305.60	209.25	19.60
PM							
Base Year	RFC	0.20	0.50	0.20	0.30	0.63	0.09
	Delay(s)	11.44	19.81	11.72	14.40	24.88	8.90
Background Growth	RFC	0.16	0.71	0.52	0.97	1.04	0.11
	Delay(s)	14.70	33.85	19.90	263.89	165.55	11.02

Effect of A12 J24 All Moves

		B-C	B-AD	A-D	D-A	D-BC	C-B
AM							
Base Year	RFC	0.23	0.51	0.33	0.30	0.79	0.24
	Delay(s)	13.23	23.20	11.02	22.81	38.67	13.34
Scenario 1	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 2	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 3	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
PM							
Base Year	RFC	0.20	0.50	0.20	0.30	0.63	0.09
	Delay(s)	11.44	19.81	11.72	14.40	24.88	8.90
Scenario 1	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 2	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC
Scenario 3	RFC	OC	OC	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC	OC	OC

A1124 – Church Hill, Earls Colne

Junction arms:

A – A1124 Church Hill

B – Upper Holt Street

C – Coggeshall Road

Existing Layout

		A	B	C
AM				
Base Year	RFC	0.70	0.65	0.41
	Delay(s)	10.74	14.77	10.25
Scenario 1	RFC	1.04	0.92	0.69
	Delay(s)	160.34	64.58	19.34
Scenario 2	RFC	1.10	0.94	0.75
	Delay(s)	279.21	72.65	23.98
Scenario 3	RFC	1.15	0.96	0.82
	Delay(s)	419.65	78.38	30.92
PM				
Base Year	RFC	0.77	0.61	0.82
	Delay(s)	14.72	12.50	25.07
Scenario 1	RFC	1.22	0.88	OC
	Delay(s)	653.16	41.96	OC
Scenario 2	RFC	1.27	0.91	OC
	Delay(s)	820.78	49.98	OC
Scenario 3	RFC	1.33	0.93	OC
	Delay(s)	991.18	60.18	OC

Background growth only

		A	B	C
AM				
Base Year	RFC	0.70	0.65	0.41
	Delay(s)	10.74	14.77	10.25
Background Growth	RFC	0.77	0.68	0.35
	Delay(s)	15.08	17.73	9.34
PM				
Base Year	RFC	0.77	0.61	0.82
	Delay(s)	14.72	12.50	25.07
Background Growth	RFC	0.91	0.67	1.21
	Delay(s)	40.19	14.79	581.79

Mitigation Layout - Signalised

		A - BC	B - A	C - AB	D - C
AM					
Scenario 1	Deg. Of Sat	91%	87.4%	87.9%	34.5%
	Delay / PCU	39.8	60	61.9	4.5
Scenario 2	Deg. Of Sat	95.1%	95.9%	92.4%	35.7%
	Delay / PCU	49.8	93.2	71.8	3.8
Scenario 3	Deg. Of Sat	98.9%	100.7%	100.9%	36.9%
	Delay / PCU	69.7	132.1	125	3.2
PM					
Scenario 1	Deg. Of Sat	110.7%	107.6%	108.6%	9.8%
	Delay / PCU	221.4	197.2	190.6	3.3
Scenario 2	Deg. Of Sat	114.8%	111.5%	112.6%	10.5%
	Delay / PCU	280.7	249.5	247.5	3.2
Scenario 3	Deg. Of Sat	117.3%	116.9%	116.6%	11.1%
	Delay / PCU	324.6	318.8	301.4	3

Head Street, Halstead

Junction arms:

- 1A – A131 Head Street (link)
- 1B – Parsonage Street
- 1C – A131 Market Hill
- 1D – A1124 Hedingham Road
- 2A – A131 Head Street
- 2B – A1124 Colchester Road
- 2C – A131 Head Street (link)

Existing Layout

		1A	1B	1C	1D	2A	2B	2C
AM								
Base Year	RFC	1.02	0.94	0.78	0.98	1.35	0.84	0.61
	Delay(s)	54.61	55.46	14.23	45.07	333.72	26.22	14.82
Scenario 1	RFC	1.12	OC	1.20	OC	1.21	0.97	0.83
	Delay(s)	331.79	OC	575.95	OC	606.28	99.17	19.72
Scenario 2	RFC	1.12	OC	1.27	OC	1.23	0.99	0.84
	Delay(s)	331.28	OC	801.53	OC	675.53	114.18	20.82
Scenario 3	RFC	1.12	OC	1.34	OC	1.25	1.01	0.85
	Delay(s)	330.58	OC	1035.18	OC	740.65	131.85	22.03
PM								
Base Year	RFC	1.02	0.98	0.92	1.00	OC	1.03	0.76
	Delay(s)	56.61	79.30	36.00	67.52	OC	100.15	26.60
Scenario 1	RFC	1.06	OC	1.30	1.30	1.32	OC	1.07
	Delay(s)	180.62	OC	908.44	899.10	928.12	OC	173.79
Scenario 2	RFC	1.05	OC	1.33	1.35	1.34	OC	1.07
	Delay(s)	179.57	OC	987.64	1050.22	1006.06	OC	169.58
Scenario 3	RFC	1.05	OC	1.35	1.39	1.36	OC	1.06
	Delay(s)	178.40	OC	1066.09	1202.89	1085.18	OC	166.06

Background growth only

		1A	1B	1C	1D	2A	2B	2C
AM								
Base Year	RFC	1.02	0.94	0.78	0.98	1.35	0.84	0.61
	Delay(s)	54.61	55.46	14.23	45.07	333.72	26.22	14.82
Background Growth	RFC	1.07	OC	0.43	0.98	0.95	0.70	0.64
	Delay(s)	148.23	OC	17.81	89.07	47.24	20.24	8.41
PM								
Base Year	RFC	1.02	0.98	0.92	1.00	OC	1.03	0.76
	Delay(s)	56.61	79.30	36.00	67.52	OC	100.15	26.60
Background Growth	RFC	1.04	OC	0.99	0.92	1.15	1.14	1.06
	Delay(s)	111.74	OC	96.60	66.71	342.27	351.96	122.94

Maldon Road – The Street, Hatfield Peverel

Junction arms:

A – The Street east

B – B1019 Maldon Road

C – The Street west

Existing Layout

		A	B	C
AM				
Base Year	RFC	0.57	0.86	0.55
	Delay(s)	9.92	26.39	7.85
Scenario 1	RFC	0.77	0.44	1.38
	Delay(s)	29.54	8.68	1157.68
Scenario 2	RFC	0.79	0.45	1.40
	Delay(s)	32.05	8.92	1203.50
Scenario 3	RFC	0.81	0.46	OC
	Delay(s)	34.78	9.16	OC
PM				
Base Year	RFC	0.56	0.75	0.90
	Delay(s)	10.22	16.48	30.29
Scenario 1	RFC	0.71	1.03	1.06
	Delay(s)	15.00	169.28	186.57
Scenario 2	RFC	0.83	1.06	1.07
	Delay(s)	16.10	225.85	219.69
Scenario 3	RFC	0.75	1.09	1.08
	Delay(s)	17.26	287.21	252.92

Background growth only

		A	B	C
AM				
Base Year	RFC	0.57	0.86	0.55
	Delay(s)	9.92	26.39	7.85
Background Growth	RFC	0.63	0.30	1.21
	Delay(s)	20.94	6.76	657.20
PM				
Base Year	RFC	0.56	0.75	0.90
	Delay(s)	10.22	16.48	30.29
Background Growth	RFC	0.48	0.81	0.91
	Delay(s)	8.67	22.94	36.21

Feering Hill – Station Road, Kelvedon

Junction arms:

A – Feering Hill

B – Swan Street

C – B1024 High Street

D – B1024 Coggeshall Road

Existing Layout

		B-ACD	A-BCD	D-ABC	C-ABD
AM					
Base Year	RFC	0.18	0.40	0.78	0.03
	Delay(s)	12.27	8.31	37.57	8.59
Scenario 1	RFC	OC	0.35	OC	0.09
	Delay(s)	OC	6.67	OC	12.23
Scenario 2	RFC	OC	0.35	OC	0.10
	Delay(s)	OC	6.45	OC	12.88
Scenario 3	RFC	OC	0.34	OC	0.10
	Delay(s)	OC	6.25	OC	13.55
PM					
Base Year	RFC	0.09	0.15	0.59	0.05
	Delay(s)	9.65	7.68	21.26	8.66
Scenario 1	RFC	0.47	0.50	OC	0.11
	Delay(s)	56.68	9.81	OC	8.90
Scenario 2	RFC	0.41	0.47	OC	0.10
	Delay(s)	45.43	9.50	OC	8.83
Scenario 3	RFC	0.38	0.45	OC	0.10
	Delay(s)	39.59	9.28	OC	8.77

Background growth only

		B-ACD	A-BCD	D-ABC	C-ABD
AM					
Base Year	RFC	0.18	0.40	0.78	0.03
	Delay(s)	12.27	8.31	37.57	8.59
Background Growth	RFC	0.18	0.30	1.05	0.07
	Delay(s)	14.00	8.05	248.04	9.09
PM					
Base Year	RFC	0.09	0.15	0.59	0.05
	Delay(s)	9.65	7.68	21.26	8.66
Background Growth	RFC	0.15	0.30	0.75	0.09
	Delay(s)	11.06	8.58	35.81	7.78

Effect of A12 J24 All Moves Junction

		B-ACD	A-BCD	D-ABC	C-ABD
AM					
Base Year	RFC	0.18	0.40	0.78	0.03
	Delay(s)	12.27	8.31	37.57	8.59
Scenario 1	RFC	0.22	0.29	1.10	0.08
	Delay(s)	18.16	6.04	352.40	12.32
Scenario 2	RFC	0.24	0.29	1.13	0.08
	Delay(s)	20.54	5.86	430.22	13.11
Scenario 3	RFC	0.27	0.28	1.17	0.09
	Delay(s)	23.63	5.69	510.49	13.98
PM					
Base Year	RFC	0.09	0.15	0.59	0.05
	Delay(s)	9.65	7.68	21.26	8.66
Scenario 1	RFC	0.15	0.41	0.80	0.08
	Delay(s)	10.53	8.71	38.56	8.54
Scenario 2	RFC	0.15	0.39	0.79	0.08
	Delay(s)	10.45	8.51	36.99	8.47
Scenario 3	RFC	0.15	0.37	0.78	0.08
	Delay(s)	10.39	8.36	35.73	8.42

Mitigation Layout – Widening of Coggeshall Road approach and new A12 J24 junction

		B-ACD	A-BCD	D-AB	D-BC	C-ABD
AM						
Base Year	RFC	0.18	0.40	0.78	N/A	0.03
	Delay(s)	12.27	8.31	37.57	N/A	8.59
Scenario 1	RFC	0.21	0.29	0.81	0.89	0.08
	Delay(s)	17.78	6.04	82.62	89.96	12.32
Scenario 2	RFC	0.23	0.23	0.95	0.94	0.08
	Delay(s)	19.99	5.86	150.76	122.70	13.11
Scenario 3	RFC	0.26	0.28	0.98	0.96	0.09
	Delay(s)	22.82	5.69	180.99	153.03	13.98
PM						
Base Year	RFC	0.09	0.15	0.59	N/A	0.05
	Delay(s)	9.65	7.68	21.26	N/A	8.66
Scenario 1	RFC	0.15	0.41	0.43	0.53	0.08
	Delay(s)	10.50	8.71	13.50	22.93	8.54
Scenario 2	RFC	0.15	0.39	0.42	0.52	0.08
	Delay(s)	10.42	8.51	13.22	22.36	8.47
Scenario 3	RFC	0.15	0.37	0.41	0.52	0.08
	Delay(s)	10.37	8.36	12.99	21.98	8.42

Rye Mill Lane, Kelvedon

Junction arms:

A – London Road

B – Inworth Road

C – Feering Hill

D – Rye Mill Lane

Existing Layout

		B-C	B-AD	A-D	D-A	D-BC	C-B
AM							
Base Year	RFC	1.07	1.05	0.03	0.07	0.05	0.41
	Delay(s)	238.29	210.76	7.23	8.01	14.89	13.40
Scenario 1	RFC	OC	OC	0.04	0.20	0.75	0.72
	Delay(s)	OC	OC	10.72	27.25	285.85	39.62
Scenario 2	RFC	OC	OC	0.04	OC	OC	0.77
	Delay(s)	OC	OC	11.01	OC	OC	50.32
Scenario 3	RFC	OC	OC	0.04	OC	OC	0.83
	Delay(s)	OC	OC	11.41	OC	OC	67.81
PM							
Base Year	RFC	0.99	1.02	0.06	0.04	0.04	0.40
	Delay(s)	170.30	146.16	7.27	6.79	14.79	11.43
PM							
Scenario 1	RFC	OC	OC	0.07	0.05	0.17	0.83
	Delay(s)	OC	OC	9.54	9.37	38.47	50.34
Scenario 2	RFC	OC	OC	0.07	0.05	0.16	0.83
	Delay(s)	OC	OC	9.33	9.13	34.98	51.07
Scenario 3	RFC	0.50	0.74	0.06	0.03	0.03	0.30
	Delay(s)	23.28	41.23	6.89	6.40	14.82	10.16

Background growth only

		B-C	B-AD	A-D	D-A	D-BC	C-B
AM							
Base Year	RFC	1.07	1.05	0.03	0.07	0.05	0.41
	Delay(s)	238.29	210.76	7.23	8.01	14.89	13.40
Background Growth	RFC	1.29	1.22	0.03	0.08	0.08	0.43
	Delay(s)	786.06	810.46	7.56	7.84	17.49	13.49
PM							
Base Year	RFC	0.99	1.02	0.06	0.04	0.04	0.40
	Delay(s)	170.30	146.16	7.27	6.79	14.79	11.43
Background Growth	RFC	0.93	0.94	0.06	0.05	0.06	0.35
	Delay(s)	154.45	125.22	7.18	6.84	12.88	10.98

Effect of A12 J24 All Moves junction

		B-C	B-AD	A-D	D-A	D-BC	C-B
AM							
Base Year	RFC	1.07	1.05	0.03	0.07	0.05	0.41
	Delay(s)	238.29	210.76	7.23	8.01	14.89	13.40
Scenario 1	RFC	OC	OC	0.03	0.07	0.08	0.01
	Delay(s)	OC	OC	7.21	7.45	16.44	8.67
Scenario 2	RFC	OC	OC	0.03	0.07	0.09	0.01
	Delay(s)	OC	OC	7.36	7.64	18.49	9.17
Scenario 3	RFC	OC	OC	0.03	0.07	0.10	0.01
	Delay(s)	OC	OC	7.51	7.84	21.12	9.72
PM							
Base Year	RFC	0.99	1.02	0.06	0.04	0.04	0.40
	Delay(s)	170.30	146.16	7.27	6.79	14.79	11.43
Scenario 1	RFC	OC	OC	0.07	0.05	0.17	0.83
	Delay(s)	OC	OC	9.54	9.37	38.47	50.34
Scenario 2	RFC	OC	OC	0.07	0.05	0.16	0.83
	Delay(s)	OC	OC	9.33	9.13	34.98	51.07
Scenario 3	RFC	0.50	0.74	0.06	0.03	0.03	0.30
	Delay(s)	23.38	41.23	6.89	6.40	14.82	10.16

Mitigation Layout – Double Mini-roundabout with new A12 J24

		1A	1B	1C	2A	2B	2C
AM							
Scenario 1	RFC	0.93	0.66	0.11	0.78	1.07	0.09
	Delay(s)	40.35	13.8	8.21	14.07	258.29	6.16
Scenario 2	RFC	1.02	0.71	0.11	0.85	1.16	0.09
	Delay(s)	106.65	16.42	8.56	20.7	484.81	6.52
Scenario 3	RFC	1.12	0.73	0.11	0.91	1.26	0.09
	Delay(s)	272.95	16.55	8.54	33.13	708.22	6.55
PM							
Scenario 1	RFC	0.80	0.44	0.05	0.72	0.59	0.19
	Delay(s)	17.19	8.42	6.78	11.36	11.96	5.71
Scenario 2	RFC	0.80	0.44	0.05	0.72	0.59	0.19
	Delay(s)	17.22	8.40	6.78	11.34	11.73	5.68
Scenario 3	RFC	0.80	0.44	0.05	0.72	0.58	0.18
	Delay(s)	17.52	8.42	6.78	11.43	11.58	5.56

Chipping Hill, Witham

Junction arms:

A – Braintree Road/Chipping Hill

B – The Avenue

C – Collingwood Road

Existing Layout

		A	B	C
AM				
Base Year	RFC	0.99	0.82	0.54
	Delay(s)	74.10	30.93	9.79
Scenario 1	RFC	1.30	1.40	0.85
	Delay(s)	926.73	1244.98	31.45
Scenario 2	RFC	1.33	OC	0.87
	Delay(s)	1022.34	OC	36.19
Scenario 3	RFC	1.36	OC	0.89
	Delay(s)	1118.44	OC	42.17
PM				
Base Year	RFC	0.80	0.96	0.67
	Delay(s)	14.71	64.40	13.92
Scenario 1	RFC	0.96	1.31	0.59
	Delay(s)	56.32	838.46	11.68
Scenario 2	RFC	0.97	1.34	0.60
	Delay(s)	68.27	918.97	11.76
Scenario 3	RFC	0.99	1.36	0.60
	Delay(s)	82.71	997.74	11.91

Background growth only

		A	B	C
AM				
Base Year	RFC	0.99	0.82	0.54
	Delay(s)	74.10	30.93	9.79
Background Growth	RFC	1.05	1.16	0.71
	Delay(s)	172.02	451.39	17.72
PM				
Base Year	RFC	0.80	0.96	0.67
	Delay(s)	14.71	64.40	13.92
Background Growth	RFC	0.73	0.93	0.54
	Delay(s)	11.05	51.77	11.13

Gershwin Boulevard, Witham

Junction arms:

A – Hatfield Road north-east

B – Gershwin Boulevard

C – Hatfield Road south-east

D – New arm

Existing Layout

		A	B	C	D
AM					
Base Year	RFC	0.49	0.34	0.44	N/A
	Delay(s)	4.48	4.48	4.35	N/A
Scenario 1	RFC	0.77	0.55	0.55	0.50
	Delay(s)	10.10	9.75	5.37	7.93
Scenario 2	RFC	0.77	0.56	0.55	0.50
	Delay(s)	10.38	9.96	5.42	8.02
Scenario 3	RFC	0.78	0.56	0.56	0.50
	Delay(s)	10.64	10.17	5.46	8.10
PM					
Base Year	RFC	0.37	0.23	0.70	N/A
	Delay(s)	3.67	3.28	7.25	N/A
Scenario 1	RFC	0.48	0.63	0.68	0.39
	Delay(s)	4.42	8.44	7.26	7.10
Scenario 2	RFC	0.48	0.65	0.69	0.40
	Delay(s)	4.47	8.96	7.36	7.20
Scenario 3	RFC	0.49	0.67	0.69	0.41
	Delay(s)	4.51	9.50	7.44	7.32

Background growth only

		A	B	C	D
AM					
Base Year	RFC	0.49	0.34	0.44	N/A
	Delay(s)	4.48	4.48	4.35	N/A
Scenario 1	RFC	0.48	0.33	0.43	N/A
	Delay(s)	4.08	4.35	3.9	N/A
PM					
Base Year	RFC	0.37	0.23	0.70	N/A
	Delay(s)	3.67	3.28	7.25	N/A
Scenario 1	RFC	0.36	0.24	0.53	N/A
	Delay(s)	3.25	3.34	4.27	N/A

Newland Street, Witham

Junction arms:

A – Newland Street north-east

B – Maldon Road

C – Newland Street south-west

D – Collingwood Road

Existing Layout

		C – A	C – B	Link SW – BC	B – CA	Link NE – DA	A – CD	D – AC
AM								
Base Year	Deg. Of Sat	40.6%	26.2%	33.9%	73.2%	43.4%	36.6%	58.3%
	Delay(s)	36.3	38.1	4.0	55.2	6.1	38.7	47.3
Scenario 1	Deg. Of Sat	56.2%	44.2%	35.1%	94.3	59.4%	OC	OC
	Delay(s)	25.9	35.8	4	180.2	8.1	OC	OC
Scenario 2	Deg. Of Sat	56.5%	45.3%	35.7%	102.8	60.4%	OC	OC
	Delay(s)	26	36.9	3.7	248.7	8.6	OC	OC
Scenario 3	Deg. Of Sat	56.8%	46.1%	36.6%	111.2	61%	OC	OC
	Delay(s)	26	37.7	3.8	341.8	8.8	OC	OC
PM								
Base Year	Deg. Of Sat	47.2%	76.9%	61.6%	80.2%	43.5%	82.3%	102.3%
	Delay(s)	36.5	91.4	6.8	64.8	6.8	55	159.5
Scenario 1	Deg. Of Sat	75.1%	73.3%	49.6%	107%	75.4%	OC	OC
	Delay(s)	40.4	66.2	3.3	294.8	12.9	OC	OC
Scenario 2	Deg. Of Sat	75.5%	74.3%	49.8%	108.6%	75.8%	OC	OC
	Delay(s)	40.6	67.7	3.2	313.8	13.1	OC	OC
Scenario 3	Deg. Of Sat	75.7%	75.5%	50.2%	109.5%	76.1%	OC	OC
	Delay(s)	40.8	69.7	3.1	323.5	13.2	OC	OC

Background growth only

		C – A	C – B	Link SW – BC	B – CA	Link NE – DA	A – CD	D - AC
AM								
Base Year	Deg. Of Sat	40.6%	26.2%	33.9%	73.2%	43.4%	36.6%	58.3%
	Delay(s)	36.3	38.1	4.0	55.2	6.1	38.7	47.3
Background Growth	Deg. Of Sat	53.8%	37.3%	51.7%	33.7%	27.4%	223.1%	227.1%
	Delay(s)	25.3	29.2	4.9	76.2	4.0	1131.4	1202.2
PM								
Base Year	Deg. Of Sat	47.2%	76.9%	61.6%	80.2%	43.5%	82.3%	102.3%
	Delay(s)	36.5	91.4	6.8	64.8	6.8	55	159.5
Background Growth	Deg. Of Sat	72.5%	53.6%	72.9%	101.9%	38.7%	201.7%	200.7%
	Delay(s)	39.1	45.6	12.1	240.3	2.9	1004.5	1079.6

Rickstones Road, Witham

Junction arms:

- 1A – Rickstones Road
- 1B – B1018 Braintree Road (link)
- 1C – B1018 Cressing Road
- 2A – B1018 Braintree Road (link)
- 2B – Cypress Road
- 2C – B1018 Braintree Road south

Existing Layout

		1A	1B	1C	2A	2B	2C
AM							
Base Year	RFC	0.58	0.77	0.97	0.90	0.69	0.67
	Delay(s)	14.73	14.10	60.85	25.76	37.68	8.43
Scenario 1	RFC	0.71	0.71	1.26	1.02	0.54	0.62
	Delay(s)	24.77	11.37	790.7	104.76	34.54	7.38
Scenario 2	RFC	0.72	0.73	1.30	1.03	0.54	0.64
	Delay(s)	25.49	12.31	917.07	111.12	35	7.79
Scenario 3	RFC	0.73	0.76	1.34	1.03	0.55	0.66
	Delay(s)	26.4	13.5	1047.62	118.62	35.48	8.28
PM							
Base Year	RFC	0.39	0.88	0.84	0.74	0.25	0.86
	Delay(s)	7.3	22.61	26.38	12	9.95	16.93
Scenario 1	RFC	0.39	0.91	1	0.85	0.47	0.86
	Delay(s)	9.03	29.28	106.15	20.99	16.93	18.96
Scenario 2	RFC	0.40	0.92	1.01	0.85	0.48	0.88
	Delay(s)	9.17	33.54	125.19	22.15	17.42	21.16
Scenario 3	RFC	0.41	0.94	1.02	0.86	0.50	0.90
	Delay(s)	9.35	40.44	143.34	23.34	18.1	24.33

Background growth only (developer layout)

		1A	1B	1C	2B – 2C	2B – 2A	2C – 2A,2B
AM							
Base Year	RFC	0.50	0.77	1.21	0.46	0.31	0.16
	Delay(s)	10.76	14.14	496.66	17.94	50.67	9.98
Background Growth	RFC	0.41	0.79	OC	OC	OC	OC
	Delay(s)	9.78	15.77	OC	OC	OC	OC
PM							
Base Year	RFC	0.40	0.89	1.06	0.23	0.27	0.30
	Delay(s)	7.56	23.6	93.68	9.63	37.06	9.09
Background Growth	RFC	0.27	0.88	1.26	OC	OC	OC
	Delay(s)	6.07	28.09	411.1	OC	OC	OC

Proposed Developer Layout

		1A	1B	1C	2B – 2C	2B – 2A	2C – 2A,2B
AM							
Base Year	RFC	0.50	0.77	1.21	0.46	0.31	0.16
	Delay(s)	10.76	14.14	496.66	17.94	50.67	9.98
Scenario 1	RFC	0.54	0.99	OC	OC	OC	OC
	Delay(s)	12.17	72.23	OC	OC	OC	OC
Scenario 2	RFC	0.55	1.02	OC	OC	OC	OC
	Delay(s)	12.32	97.07	OC	OC	OC	OC
Scenario 3	RFC	0.56	1.05	OC	OC	OC	OC
	Delay(s)	12.53	128.03	OC	OC	OC	OC
PM							
Base Year	RFC	0.40	0.89	1.06	0.23	0.27	0.30
	Delay(s)	7.56	23.6	93.68	9.63	37.06	9.09
Scenario 1	RFC	0.36	0.98	OC	OC	OC	OC
	Delay(s)	7.79	59.94	OC	OC	OC	OC
Scenario 2	RFC	0.37	0.99	OC	OC	OC	OC
	Delay(s)	7.83	68.71	OC	OC	OC	OC
Scenario 3	RFC	0.37	1.00	OC	OC	OC	OC
	Delay(s)	7.89	82.89	OC	OC	OC	OC

Mitigation Layout – Signalised Junction

A – Rickstones Road

B – Cypress Road

C – Braintree Road

D – Cressing Road

		A	B	C	D
AM					
Scenario 1	Deg. Of Sat	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC
Scenario 2	Deg. Of Sat	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC
Scenario 3	Deg. Of Sat	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC
PM					
Scenario 1	Deg. Of Sat	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC
Scenario 2	Deg. Of Sat	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC
Scenario 3	Deg. Of Sat	OC	OC	OC	OC
	Delay(s)	OC	OC	OC	OC

Appendix H: Junction Mitigation Designs




Notes


- 1. Do not scale.
- 2. Design shown is indicative only and based on Ordnance Survey data. A full topographical survey is required to develop the design and ensure buildability.

Key


- Proposed footway
- Proposed additional carriageway
- Proposed physical boundary
- Proposed areas of road markings
- Proposed kerb
- Proposed PCC edging



Rev	Date	Description of revision	Drawn	Checked	Reviewed	Approved
CHECK PRINT						
DRAWING STATUS						
FEASIBILITY						
 Integrated expertise  Essex County Council						
Mark Rowe, Service Director, Highways Seax House, Victoria Road South, Chelmsford, CM1 1QH. Tel: 0345 6037631 © Essex County Council						
SCHEME TITLE						
BRAINTREE LOCAL PLAN SUPPORT						
DRAWING TITLE						
A131 BROAD ROAD						
DESIGNED	DRAWN	CHECKED	REVIEWED	APPROVED		
...	BA					
DATE	DATE	DATE	DATE	DATE		
NOV 16	NOV 16					
DRAWING UNITS U.N.O.				SCALE AT A3 (420x297mm)		
DIMENSIONS IN MILLIMETRES				1:1250		
LEVELS IN METRES						
DRAWING No.						REV.
B3553R5D-01-AD-00-001						-



Rev	Date	Description of revision	Drawn	Checked	Review'd	Approv'd
CHECK PRINT						
DRAWING STATUS						
FOR COSTING ONLY						
 Integrated expertise 						
Mark Rowe, Service Director, Highways Seax House, Victoria Road South, Chelmsford, CM1 1QH. Tel: 0345 6037631 © Essex County Council						
SCHEME TITLE						
BRAINTREE LOCAL PLAN SUPPORT						
DRAWING TITLE						
A131 CUCKOO WAY, GREAT NOTLEY						
DESIGNED	BA	DRAWN	BA	CHECKED	REVIEWED	APPROVED
DATE	NOV 16	DATE	NOV 16	DATE	DATE	DATE
DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES					SCALE AT A3 (420x297mm) 1:1000	
DRAWING No. B3553R5D-02-AD-00-001						REV. -



- Notes**
- 1. Do not scale.
 - 2. Design shown is indicative only and based on Ordnance Survey data. A full topographical survey is required to develop the design and ensure buildability.

Key

Proposed additional carriageway

Proposed kerbs

Rev	Date	Description of revision	Drawn	Checked	Review'd	Approv'd
CHECK PRINT						
DRAWING STATUS						
FOR COSTING ONLY						
 Integrated expertise  Essex County Council						
Mark Rowe, Service Director, Highways Seax House, Victoria Road South, Chelmsford, CM1 1QH. Tel: 0345 6037631 © Essex County Council						
SCHEME TITLE						
BRAINTREE LOCAL PLAN SUPPORT						
DRAWING TITLE						
A131 LONDON ROAD, GREAT NOTLEY						
DESIGNED	BA	DRAWN	BA	CHECKED	REVIEWED	APPROVED
DATE	NOV 16	DATE	NOV 16	DATE	DATE	DATE
DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES					SCALE AT A3 (420x297mm) 1:500	
DRAWING No. B3553R5D-03-AD-00-001						REV. -

WORKING COPY

1. Do not scale.
2. Design shown is indicative only and based on Ordnance Survey data. A full topographical survey is required to develop the design and ensure buildability.

-  Proposed footway
-  Proposed additional carriageway
-  Proposed island
-  Proposed Kerb
-  Proposed PCC edging
-  Proposed primary traffic signal
-  Proposed secondary traffic signal

Headwalls will be required before ditch is filled

+ 61.5m

New footpath for continuity with opposite side

Rev.	Date	Description of revision	Drawn	Checked	Review'd	Approv'd

CHECK PRINT

DRAWING STATUS

FEASIBILITY



Mark Rowe, Service Director, Highways
Seax House, Victoria Road South, Chelmsford, CM1 1QH.
Tel: 0345 6037631 © Essex County Council

SCHEME TITLE	
BRAINTREE LOCAL PLAN SUPPORT	

DRAWING TITLE

DEANERY HILL, BRAINTREE

DESIGNED BA	DRAWN BA	CHECKED	REVIEWED	APPROVED
DATE NOV 16	DATE NOV 16	DATE	DATE	DATE

DRAWING UNITS I.N.O.	SCALE AT A3 (420x297mm)
DIMENSIONS IN MILLIMETRES	1:500
LEVELS IN METRES	

DRAWING No.	REV.
B3553R5D-06-AD-00-001	-

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Essex County Council, 100019602, 2016

File Location N:\9 Trans Impr\2 Major Projects Design\1 Projects\B3553R5D_Braintree Local Plan Support\03_CAD\Advance Design\06_Deanery Hill Braintree\B3553R5D-06-AD-00-001.dwg Last saved by brad.antliff on 5 December 2016 Printed By Brad Antliff on 5 December 2016

WORKING COPY



- Notes:**
- Do not scale.
 - This drawing is to be read in conjunction with all other contract drawings and documents.

- Key**
- Highway Boundary
 - Proposed Precast Concrete HB2 Kerb as per Essex folio EB100
 - Proposed Edging Kerb (EF 150) laid flush with footway as per Essex folio EB102
 - Proposed Carriagewa
 - Proposed Slope Embankment Area
 - Proposed Shared Footway/Cycleway
 - Existing Footway
 - Resurface Existing Carriageway
 - Existing landscaping
 - Proposed landscaping
 - Proposed Road Marking

Rev	Date	Description of revision	Drawn	Checked	Reviewed	Approved

DRAWING STATUS

STAGE 2 - SCHEME IDENTIFICATION



Mark Rowe, Service Director, Highways
Seax House, Victoria Road South, Chelmsford, CM1 1QH.
Tel: 0345 6037631 © Essex County Council

SCHEME TITLE


SPRINGWOOD DRIVE/PODS BROOK ROAD JUNCTION IMPROVEMENTS

DRAWING TITLE

**H-4A OPTION 6
IMPROVED ROUNDABOUT**

SAFETY, HEALTH AND ENVIRONMENTAL BOX					
In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following:					
Hazard Log Ref	DESCRIPTION OF HAZARDS				
1.	No stats info provided so care is to be taken when excavating for new footway				

DESIGNED	DRAWN	CHECKED	REVIEWED	APPROVED
RS	AG	BB	PM	BS
DATE	DATE	DATE	DATE	DATE
NOV 16	NOV 16	NOV 16	NOV 16	NOV 16
DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES				SCALE AT A3 (420x297mm) 1:1000
DRAWING No. B355307A-H4A-00-006				REV. -



- Notes
1. Do not scale.
 2. Design shown is indicative only and based on Ordnance Survey data. A full topographical survey is required to develop the design and ensure buildability.

- Key
- Proposed footway
 - Proposed additional carriageway
 - Proposed islands
 - Proposed kerbs
 - Proposed PCC edging
 - Proposed primary traffic signal
 - Proposed secondary traffic signal

Rev.	Date	Description of revision	Drawn	Checked	Reviewed	Approved

DRAWING STATUS

FOR COSTING ONLY



Mark Rowe, Service Director, Highways
Seax House, Victoria Road South, Chelmsford, CM1 1QH.
Tel: 0345 6037631 © Essex County Council

SCHEME TITLE


BRAINTREE LOCAL PLAN
SUPPORT

DRAWING TITLE

A1124 CHURCH HILL,
EARLS COLNE


DESIGNED BA	DRAWN BA	CHECKED	REVIEWED	APPROVED
DATE NOV 16	DATE NOV 16	DATE	DATE	DATE
DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES				SCALE AT A3 (420x297mm) 1:500
DRAWING No. B3553R5D-04-AD-001				REV. -

WORKING COPY



- Notes
1. Do not scale.

Rev.	Date	Description of revision	Drawn	Checked	Reviewed	Approved
CHECK PRINT						
DRAWING STATUS						
FEASIBILITY						
						
Mark Rowe, Service Director, Highways Seax House, Victoria Road South, Chelmsford, CM1 1QH. Tel: 0345 6037631 © Essex County Council						
SCHEME TITLE						
BRAINTREE LOCAL PLAN SUPPORT						
DRAWING TITLE						
FEERING HILL STATION ROAD KELVEDON						
DESIGNED BA	DRAWN BA	CHECKED	REVIEWED	APPROVED		
DATE NOV 16	DATE NOV 16	DATE	DATE	DATE		
DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES				SCALE AT A1 (841X594mm) 1:200		
DRAWING No. B3553R5D-07-AD-00-001				REV. -		



- Notes
1. Do not scale.
 2. Design shown is indicative only and based on Ordnance Survey data. A full topographical survey is required to develop the design and ensure buildability.

- Key
- Proposed footway
 - Proposed additional carriageway
 - Proposed island
 - Proposed Kerb
 - Proposed primary traffic signal
 - Proposed secondary traffic signal

Rev	Date	Description of revision	Drawn	Checked	Review'd	Approv'd
CHECK PRINT						
DRAWING STATUS						
FEASIBILITY						
 Integrated expertise 						
Mark Rowe, Service Director, Highways Seax House, Victoria Road South, Chelmsford, CM1 1QH. Tel: 0345 6037631 © Essex County Council						
SCHEME TITLE						
BRAINTREE LOCAL PLAN SUPPORT						
DRAWING TITLE						
RYE MILL LANE, KELVEDON						
DESIGNED	BA	DRAWN	BA	CHECKED	REVIEWED	APPROVED
DATE	NOV 16	DATE	NOV 16	DATE	DATE	DATE
DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES					SCALE AT A3 (420x297mm) 1:500	
DRAWING No. B3553R5D-08-AD-00-001						REV. -

WORKING COPY

Appendix I: Existing Bus Links to Developments


Site Reference	Direct Bus Link	Buses /hour AM	Buses /hour PM	Existing bus stop	Bus link <400m	Buses /hour AM	Buses /hour PM	Existing bus stop <400m	Comments
Residential									
BOCN123	N	-	-	-	Y	7 to 10	5 to 7	Y	Closest bus link on B1053 Broad Road
BOCN127	N	-	-	-	Y	5 to 7	3 to 5	Y	Closest bus link on B1053 Broad Road
BOCS140	Y	3 to 5	2 to 3	Y	-	-	-	-	Bus link on Rayne Road
BRAW153	N	-	-	-	Y	3 to 5	2 to 3	Y	Bus link on Rayne Road
BCBG149	N	-	-	-	Y	3 to 5	5 to 7	Y	Bus link on Cressing Road, Chapel Hill and B1018. values here given for closest bus stop on Cressing Road
BCBG550	N	-	-	-	Y	3 to 5	5 to 7	Y	Bus link on Cressing Road, Chapel Hill and B1018. values here given for closest bus stop on Cressing Road
WITN425	Y	7 to 10	7 to 10	Y	-	-	-	-	Lots of bus links near train station
WITC421	N	-	-	-	Y	10 to 15	7 to 10	Y	Bus link on B1389 Newland Street
WITW431	N	-	-	-	Y	2 to 3	2 to 3	Y	Bus link within 400m on Humber Road
HATF314/315	Y	7 to 10	5 to 7	Y	-	-	-	-	Bus stop going east easily accessible but bus stop going west, having to cross high speed road with islands in between
BURE165/166	N	-	-	-	Y	3 to 5	3 to 5	Y	Bus link on Colchester Road approx. 300m away
CRESS201	Y	2 to 3	3 to 5	Y	-	-	-	-	Bus link on Polecat Road
HASA295	Y	1	2 to 3	Y	-	-	-	-	Bus link on Fenn Road

Site Reference	Direct Bus Link	Buses /hour AM	Buses /hour PM	Existing bus stop	Bus link <400m	Buses /hour AM	Buses /hour PM	Existing bus stop <400m	Comments
HASA289	N	-	-	-	Y	2 to 3	2 to 3	Y	Bus link on Fenn Road
KELV335	N	-	-	-	N	-	-	-	Nearest bus link on Kelvedon High Street approx. 600m
SIBH377	N	-	-	-	N	-	-	-	Bus link approx 500m away on Yeldham Road A1017
EAR1475	N	-	-	-	N	-	-	-	Bus link approx. 470m away on A1124 Halstead Road
HAT ARLA	N	-	-	-	N	-	-	-	Bus link just over 400m away on B1137 The Street used, for frequency see HAT 545
HAT545	N	-	-	-	Y	15 to 20	10 to 15	N	Bus link on B1137 The Street. Bus stop only just over 400m, most likely not worth putting new bus stop on this route
Mixed									
BOCN132	Y	7 to 10	5 to 7	Y	-	-	-	-	No bus link on A131, only on Broad Road
BOCN137	Y	2 to 3	1	Y	-	-	-	-	Bus link on Deanery Hill
COGG506	Y	7 to 10	10 to 15	Y	-	-	-	-	Bus link on West Street
FEER232/230/233	Y	3 to 5	3 to 5	Y	-	-	-	-	Values taken from Inworth Road as worst case scenario, more frequent service on London Road
BLAN114/115	Y	10 to 15	10 to 15	Y	-	-	-	-	On the western boundary there are 10 to 15 per hour in the AM and there are another bus link on the eastern boundary with 1 to 2 buses per hour in the PM
GRSA269	Y	5 to 7	3 to 5	Y	-	-	-	-	Bus link used on Rayne Road

Site Reference	Direct Bus Link	Buses /hour AM	Buses /hour PM	Existing bus stop	Bus link <400m	Buses /hour AM	Buses /hour PM	Existing bus stop <400m	Comments
FFER231	Y	7 to 10	7 to 10	Y	-	-	-	-	Land access assumed was Coggeshall Road, could also be from A12
Confirmed									
GNBN264	Y	15 to 20	15 to 20	Y	-	-	-	-	Bus stop 360m away on London Road
BRSO152	Y	7 to 10	3 to 5	Y	-	-	-	-	Bus stop at the rail station
WITHN426/427	Y	7 to 10	7 to 10	Y	-	-	-	-	Bus link on Conrad Road
HASA513	Y	5 to 7	3 to 5	Y	-	-	-	-	Bus link on Colchester Road
EARC225	Y	5 to 7	5 to 7	Y	-	-	-	-	Bus link on Halstead Road
EAR3H	Y	-	-	-	Y	5 to 7	5 to 7	Y	Technically there is a directly bus link on Station Road but it doesn't run 1 service an hour in the AM/PM peak. Bus link nearby on A1124 Halstead Road
EAST ST	N	-	-	-	Y	7 to 10	7 to 10	Y	Two bus links within 400m to the north and south, values given from southern link as it was slightly closer on the B1018, northern bus link on B1256 Coggeshall Road
PANF	Y	1	1	Y	-	-	-	-	Bus link on Panfield Lane
GRNO260	N	-	-	-	N	-	-	-	Closest bus link approx. 600m on Notley Green with frequency of 2 to 3 in AM and PM
RIVE360	Y	2 to 3	2 to 3	Y	-	-	-	-	Bus link on Forest Road
WITC423	Y	7 to 10	10 to 15	N	-	-	-	-	Bus link used here on Hatfield Road. Another one on the NE boundary on Allectus Way

Site Reference	Direct Bus Link	Buses /hour AM	Buses /hour PM	Existing bus stop	Bus link <400m	Buses /hour AM	Buses /hour PM	Existing bus stop <400m	Comments
Employment									
BOCS138	N	-	-	-	N	-	-	-	Bus link approx. 670m away on Rayne Road
RIVE362/363	N	-	-	-	Y	5 to 7	3 to 5	N	Nearby bus link is A12 but closest bus stop on Colchester Road/Colemans Bridge
EARC2276	N	-	-	-	N	-	-	-	Bus link approx. 3.5km away on A1124 Halstead Road
GOSF249	N	-	-	-	N	-	-	-	Bus link approx. 600m away on A1017 Hedingham Road
RIVE364	Y	5 to 7	3 to 5	Y	-	-	-	-	Bus stop going westbound accessible but would have to cross the A12 for bus stop going eastbound
COLE188	Y	5 to 7	3 to 5	Y	-	-	-	-	Site access assumed to be Colchester Road. Existing bus stop approx. 450m away


Appendix J: Bus Frequencies



Bus Network Frequency		
30 to 90	(322)	
20 to 30	(542)	
15 to 20	(920)	
10 to 15	(1682)	
7 to 10	(2387)	
5 to 7	(2823)	
3 to 5	(3594)	
2 to 3	(2832)	
1 to 1	(3237)	
0 to 0	(4443)	

REV	DATE	DRAWING NUMBER	DRAWN	CHECKED
--	07/11/16	B3553R5D	LK	CF
DRAWING STATUS				
FINAL				
 integrated expertise  Essex County Council				
Mark Rowe, Service Director, Essex Highways County Hall, Chelmsford, CM1 1QH Tel: 0345 6037631 © Essex County Council				
SCHEME TITLE				
BRAINTREE LOCAL PLAN				
DRAWING TITLE				
BRAINTREE BUS FREQUENCY NETWORK AM				
DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES			SCALE AT A3 (420x297mm) AS SHOWN	

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office
© Crown Copyright. Unauthorised reproduction infringes Crown Copyright
and may lead to prosecution or civil proceedings. Essex County Council, 100019602, 2016




Bus Network Frequency		
30 to 110	(480)	
20 to 30	(614)	
15 to 20	(750)	
10 to 15	(1656)	
7 to 10	(2046)	
5 to 7	(2583)	
3 to 5	(3713)	
2 to 3	(3297)	
1 to 1	(3363)	
0 to 0	(4280)	

REV	DATE	DRAWING NUMBER	DRAWN	CHECKED
--	07/11/16	B3553R5D	LK	CF
DRAWING STATUS				
FINAL				
 integrated expertise  Essex County Council				
Mark Rowe, Service Director, Essex Highways County Hall, Chelmsford. CM1 1QH Tel: 0345 6037631 © Essex County Council				
SCHEME TITLE				
BRAINTREE LOCAL PLAN				
DRAWING TITLE				
BRAINTREE BUS FREQUENCY NETWORK PM				
DRAWING UNITS U.N.O DIMENSIONS IN MILLIMETRES LEVELS IN METRES			SCALE AT A3 (420x297mm) AS SHOWN	

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office
© Crown Copyright. Unauthorised reproduction infringes Crown Copyright
and may lead to prosecution or civil proceedings. Essex County Council, 100019602, 2016

Appendix K: Potential bus links to developments



Development Type

- Residential
- Mixed
- Employment
- Confirmed
- District Boundary
- Possible New Bus Route

REV	DATE	DRAWING NUMBER	DRAWN	CHECKED
0	07/11/16	B3553R5D	LK	CF

DRAWING STATUS
DRAFT



Mark Rowe, Service Director, Essex Highways
County Hall, Chelmsford. CM1 1QH
Tel: 0345 6037631
© Essex County Council

BRAINTREE LOCAL PLAN:
PREFERRED OPTION ASSESSMENT


DRAWING TITLE
PREFERRED OPTION

DRAWING UNITS
DIMENSIONS IN MILLIMETRES
LEVELS IN METRES

SCALE AT A3 (420x297mm)
AS SHOWN

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office
© Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Essex County Council, 100019602, 2016

Appendix L: Potential cycle links to developments



Key

- Essex Cycle Network
- Braintree Proposed Cycle Routes

Development Type

- Confirmed
- Employment
- Mixed
- Residential

Potential Connections to Proposed and Existing Cycle Network

-

REV	DATE	DRAWING NUMBER	DRAWN	CHECKED
0	21/11/16	B3553R5D	LK	CF

DRAWING STATUS
FINAL



Mark Rowe, Service Director, Essex Highways
County Hall, Chelmsford, CM1 1QH
Tel: 0345 6037631
© Essex County Council


SCHEME TITLE
**BRAINTREE LOCAL PLAN:
PREFERRED OPTION ASSESSMENT**

DRAWING TITLE
**PREFERRED OPTION
POTENTIAL CYCLE ROUTES**

DRAWING UNITS
U.N.O
DIMENSIONS IN MILLIMETRES
LEVELS IN METRES

SCALE AT A3 (420x297mm)
AS SHOWN

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office
© Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Essex County Council, 100019602, 2016



Key

Essex Cycle Network

Halstead Proposed Cycle Routes

Development Type

Confirmed

Employment

Mixed

Residential

Potential Connections to Proposed and Existing Cycle Network

REV	DATE	DRAWINGNUMBER	DRAWN	CHECKED
0	21/11/16	B3553R5D	LK	CF

DRAWING STATUS

FINAL



integrated expertise



Essex County Council

Mark Rowe, Service Director, Essex Highways
County Hall, Chelmsford. CM1 1QH
Tel: 0345 6037631
© Essex County Council

SCHEME TITLE

BRAINTREE LOCAL PLAN:
PREFERRED OPTION ASSESSMENT


DRAWING TITLE

PREFERRED OPTION
POTENTIAL CYCLE ROUTES

DRAWING UNITS U.N.O.
DIMENSIONS IN MILLIMETRES
LEVELS IN METRES

SCALE AT A3 (420x297mm)
AS SHOWN

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office
© Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Essex County Council, 100019602, 2016



This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office
© Crown Copyright. Unauthorised reproduction infringes Crown Copyright
and may lead to prosecution or civil proceedings. Essex County Council, 100019602, 2016

Key

- Essex Cycle Network
- Witham Proposed Cycle Routes

Development Type

- Confirmed
- Employment
- Mixed
- Residential

Potential Connections to
Proposed and Existing Cycle
Network

REV	DATE	DRAWING NUMBER	DRAWN	CHECKED
0	21/11/16	B3553R5D	LK	CF

DRAWING STATUS
FINAL

**RINGWAY
JACOBS**
integrated expertise

Essex County Council

Mark Rowe, Service Director, Essex Highways
County Hall, Chelmsford, CM1 1QH
Tel: 0345 6037631
© Essex County Council

SCHEME TITLE

**BRAINTREE LOCAL PLAN:
PREFERRED OPTION ASSESSMENT**

DRAWING TITLE

**PREFERRED OPTION
POTENTIAL CYCLE ROUTES**

DRAWING UNITS U.N.O. DIMENSIONS IN MILLIMETRES LEVELS IN METRES	SCALE AT A3 (420x297mm) AS SHOWN
--	-------------------------------------